



Quarterly Program Review

July 25, 2001

Washington, DC

***Distributed Utility Integration Test
DUIT***

DUA

Endecon Engineering

PG&E

Exelon (PECO)

CEC

Salt River Project

Encorp

Caterpillar

Solar Turbines

Onsite Energy

SMUD

Niagara Mohawk

Distributed Utility Integration Test

- 1) Build a team
 - 2) Document appropriate technologies
 - 3) Document features of appropriate site(s)
 - 4) Develop a project plan
 - 5) Develop a project plan for a DUIT facility at the Nevada Test Site
- Ω One year contract - Completion scheduled Oct. 2001
 - Ω NREL Technical Monitor: Ben Kroposki
 - Ω DUIT team leaders: Joe Iannucci, Susan Horgan, Chuck Whitaker

Task 1: Integration Test Stakeholder Outreach and Consensus Building

Deliverable: Integration Test Concept Paper

→ description of and rationale for the DUIT Project

- ∞ As DP becomes more commonplace its electrical interactions will become more important to understand and more challenging to manage.**
- ∞ DUIT will attempt to discover the challenges and benefits that will result from the extensive use of distributed energy resources.**
- ∞ DUIT will help to define the distribution system of the future.**

DUIT Plan:

Technology Selection and Evaluation

Site Assessment and Selection

Identification of Electrical and Operational Issues

Potential Results and Policy Implications

Statement of work, costs and schedule

Task 2: DUIT Site Assessment

Objective:

- Ω Evaluate potential test locations and recommend optimum site (or combination of sites), operation and testing of distributed generation technologies by the DUIT project.
- Ω Includes an assessment for each site
- Ω Completed July 2001

Sites Evaluated

Detailed facility information was obtained from the following locations for evaluation as DUIT testing sites:

- Ω Dolan Test Center – Groveport, OH
- Ω Modular Generation Test Facility (MGTF) – San Ramon, CA
- Ω National Renewable Energy Laboratories (NREL) – Golden, CO
- Ω Oak Ridge National Laboratory – Oak Ridge, TN
- Ω Pacific Northwest National Laboratories (PNNL) – Hanford, WA
- Ω Power Electronics Applications Center (PEAC) – Knoxville, TN
- Ω Sandia National Laboratories – Albuquerque, NM
- Ω Solar Test and Research (STAR) Facility – Phoenix, AZ
- Ω Southwest Research Institute (SWRI) – San Antonio, TX
- Ω University of California at Irvine – Irvine, CA
- Ω University of Wisconsin – Madison, WI

Other Sites Considered

Several other locations were investigated but ruled out for in-depth evaluation. These included:

- ∩ Colorado State University – Fort Collins, CO
- ∩ DTE Technology Solutions – Novi, MI
- ∩ Foothills Training Facility (APS) – Tempe, AZ
- ∩ Greenhouse Gas Verification Center – Research Triangle Park, NC
- ∩ Underwriters Laboratories (UL)

Site Assessment Criteria

- Ω Available space – number of test cells or bays, their sizes, and limitations
- Ω MW Rating – largest single DR allowable; total allowed DG for facility
- Ω Existing/permanent DRs on-site – potential for reducing acquisition costs of new equipment
- Ω Existing testing equipment – controls, monitoring and instrumentation, switching load banks, etc.
- Ω Host utility's level of interest, support and involvement, both financial and in terms of personnel time and expertise
- Ω Ability to test in both radial and network circuit configurations
- Ω Grid supply – voltage, MVA, switching arrangements, and limitations
- Ω Fuel supply and storage – natural gas line size, pressure and flow rate (BTU/hr); diesel, hydrogen, gasoline, LPG availability and/or storage capability

Site Assessment Criteria

- Ω Flexibility of facility to evolve or adapt to future/unforeseen testing needs
- Ω Limitations – noise, emissions, other
- Ω Ability to test multiple DRs at once, in interactive modes
- Ω Number and expertise of testing staff
- Ω Testing history/experience relevant to DUIT
- Ω Costs - for required facility upgrades to accommodate DUIT testing, as well as for the testing itself. Factors to consider:
 - cost of DR technologies (purchase, rental, lease, O&M, fuel, etc.)
 - number of DR installations and removals
 - duration of tests
 - fuel costs
 - analysis and reporting requirements
 - requirements of host utility (meetings, trips, etc.)
 - special installation equipment required
 - control equipment for multiple DRs

Task 3: Technology Evaluation, Selection and Availability

Deliverable: Technology Selection Report

Ω Rotating DR

- **Synchronous MG-sets**
- **Induction Generator Systems**

Ω Grid Tie Inverters

Ω Inverter Based DR

- **Fuel Cell**
- **Photovoltaic**
- **Microturbine**

Ω Storage Technologies

- **Flywheel**
- **SMES**
- **Conventional and Advanced Electrochemical**

Inverter Supplier Table (Partial)

Supplier	Electrical Rating	Physical Size	Weight	Venting Requirements	Fuel Requirements	Indoor/Outdoor Rating	Ambient Temperature
Advanced Energy Systems Aerovironment	1KVA	19"Hx8"Wx6.5"D	43 Lbs.	None	None	Full outdoor	-40Deg. C 60Deg.C
Xantrex/Trace Eng. Model ST	1 - 2.5	33.5"Hx13.25"Wx5.3"D	35 Lbs.	None	None	Indoor, outdoor with optional rain shield	-39Deg. C 45Deg. C
Xantrex/Trace Tech. Model PV 10	10KVA	26"Hx18"Wx10"D	75 Lbs.	None	None	NEMA 4 outdoor rating	-20Deg.C 50Deg.C
Xantrex/Trace Tech Model PV 15, 20	15 – 20 KVA	30"Hx25"Wx13"D	175 Lbs.	None	None	NEMA 4 outdoor rating	-20Deg. C 50Deg. C
S&C Omnion Model 2400	2.2 – 6 KVA	28"Hx18"Wx8"D	74 Lbs.	None	None	NEMA 3R outdoor rating	-20Deg. C 40 Deg.C (45 for some products)
S&C Omnion Model 2500	1- 2 KVA	21.75"Hx12"Wx7.25"D	1KVA – 35 Lbs. 2KVA – 40 Lbs.	None	None	NEMA 3R IP 32	-25 Deg. C 50 Deg. C
S&C Omnion	50 – 100KVA	75"Hx76"Wx38"D	50KVA – 2000 Lbs. 100KVA – 2200Lbs.	None	None	NEMA 3R	-30 Deg. C 50 Deg.C
Vanner Model RE24-4500DGT	4.5KVA	29"Hx20.5"Wx9.25"D	95 Lbs.	None	None	N.A.	4.5KVA@ 25Deg.C

Task 4: DUIT Project Plan

DUIT Plan:

- ∩ **Technology plans**
- ∩ **Site specification**
- ∩ **Test Plan**
- ∩ **DAS requirements**
- ∩ **Costs and schedule**

Test Plan: Issues for All Tests

- ∞ **High DR penetration levels**
- ∞ **Legacy distribution systems**
- ∞ **Future distribution systems**
- ∞ **Interaction Between Different Distributed Resources**
- ∞ **Distributed Resource Types**
 - **Rotating: synchronous and induction**
 - **Inverter-based: fuel cell, storage, PV, microturbine**

Task 4: Test Plan

Ω **Power Quality**

- **Harmonics**
- **Power Factor**
- **Flicker**
- **DC Injection**
- **EMI/EMF**
- **Type Testing vs. Aggregate Testing**
- **Start-up vs. Long-term**

Test Plan: System Protection

∞ **Abnormal Conditions**

- Voltage trip points
- Frequency trip points
- Fault detection

∞ **Islanding**

- Inadvertent
- Intentional

∞ **Synchronization**

∞ **Immunity Protection**

Test Plan: Distribution System Interaction

- ∩ **Network Systems**
- ∩ **Fuse Protection**
- ∩ **Recloser Coordination**
- ∩ **Short Circuit Current Contribution**
- ∩ **Voltage regulation - incidental and intentional**
- ∩ **Substation backfeed**

Test Plan Protocols - Format

- Ω **Brief Background on Test Topic**
- Ω **Governing IEEE 1547 Sections**
- Ω **Other Governing Standards and Sections (e.g., UL 1741, California Rule 21)**
- Ω **Test Objectives**
- Ω **Key Testing Parameters**
- Ω **Expected Results**
- Ω **Test Procedure**
- Ω **Data Acquisition Requirements**
- Ω **Control Requirements**
- Ω **Facility Requirements**
- Ω **DR Requirements**
- Ω **Other Requirements**
- Ω **Modeling Input Required**

Testing Protocols - Status

In Draft and Out for Review:

- Ω **Anti Islanding - 4**
- Ω **Substation Backfeed - 1**
- Ω **Sectionalizer Test - 2**
- Ω **Cold Load Pick-up - 1**
- Ω **Reclosing Coordination - 1**
- Ω **Synchronization - 1**
- Ω **Short Circuit Current - 2**
- Ω **Stability - 2**
- Ω **Fuses - 2**

Nearly Complete:

- Ω **Voltage Regulation - 2**
- Ω **Capacitor Switching-1**

To Be Completed:


- Ω **Additional Islanding - 3 to 5**
- Ω **Control Strategies**
- Ω **Network Systems**
- Ω **Abnormal Conditions**
- Ω **Power Quality**
- Ω **Faults on Adjacent Feeders**
- Ω **O & M / Periodic Testing Needs**

Task 5: NTS

Distributed Power Test and Demonstration Plan

Area 57


Area 25



Area 25 Jackass Flats Substation

Substation
25-10

Proposed
DP Test
Area



Feeder 1202


Feeder 25-1202 at Nevada Test Site




NTS Inventory and Assets

- Ω Existing 2.5 MVA substation with two branch circuits
- Ω Multiple building loads
- Ω Wall mounted switch gear for tie in
- Ω Load banks available
- Ω Diesel gensets available
- Ω 2.0 kW photovoltaic system
- Ω Fuel availability (Diesel) **Liquid Natural Gas (LNG) Minimal permitting processes for fuels and environmental
- Ω Spare electrical equipment
- Ω Transformers, poles, conductors, switch gear
- Ω Phone and data lines available at building locations


Conceptual NTS Test Facility



NTS DPP Facility - Multi-Layer Pole to Pole Concept



DUIT Test Facility - Row Spacing of Poles



DUIT Test Facility - Attributes

- ∞ **Co-location of distributed resources and loads**
- ∞ **Real world distribution system field with 32 miles of feeder**
- ∞ **Distribution field can be configured as a network system**
- ∞ **Makes use of NTS material and personnel resources**
- ∞ **Flexible DAS for monitoring DR and loads**
- ∞ **Conducive to annual upgrades and project phasing**

Potential Project Phasing

- ∞ Low voltage testing
- ∞ Medium voltage, lumped parameter (impedances) DS testing
- ∞ Medium voltage, Distribution system feeder yard
 - *Need to understand cost /benefit of lumped parameter vs. feeder yard*
 - *Some unique features of NTS that suggest feeder yard may be more economical*

Concept Test Facility - Needs

- ∩ **Additional poles for the build-out of the distribution system field**
- ∩ **Additional concrete pads for DG and loads areas**
- ∩ **Cable and conductor for distribution system field and interconnection areas**
- ∩ **Extensive DAS for test monitoring**
- ∩ **Hardware for low and medium voltage interconnect areas**
- ∩ **Fencing for distribution field and interconnect areas**

Deliverables Task 1-5

Deliverable Description

Due

Concept Paper on DUIT (Task 1)

Complete

Site Assessment Report (Task 2)

Complete

Technology Selection Report (Task 3)

Complete

Detailed Project Plan for DUIT (Task 4)

10/1/01

Detailed Project Plan for NTS (Task 5)

10/1/01

Final Report

10/30/01




Back-up Slides: Test Plan Example

DUIT Test Plan: Sectionalizing Devices

Objective: Determine how the presence of DR on a feeder affects the operation of sectionalizers and their coordination with other protective systems, particularly reclosers.

- Ω Momentary (cleared) faults: the recloser should operate to restore the feeder before the sectionalizer operates.**
- Ω Sustained faults: the sectionalizer should operate for downstream faults before the recloser locks out.**
- Ω Need to determine under what specific scenarios and configurations DR causes sectionalizer to misoperate.**

Sectionalizer Test - Schematic



Key Test Parameters

- ∩ **Fault location and type: 1- Φ , Φ - Φ , 3- Φ , bolted, high-Z**
- ∩ **Penetration level: number and size(s) of DRs**
- ∩ **Export vs. non-export conditions**
- ∩ **Stiffness ratio of system**
- ∩ **Length of feeder**
- ∩ **Types of DRs: synchronous, induction, inverter-based**
- ∩ **Types and sizes of loads**
- ∩ **Impedances between key points and devices**

Test Procedure

- Ω **Set up system without DR; verify correct operation of sectionalizer for fault conditions (baseline case).**
- Ω **Add DR to system.**
- Ω **Simulate faults of required types and locations.**
- Ω **Monitor and record recloser and sectionalizer operations and system voltages.**
- Ω **Vary test by (as needed):**
 - **export/non-export**
 - **DR number and power level**
 - **system stiffness**
 - **feeder length**

Data Acquisition Requirements

Parameter	Units	Range	Accuracy	Sampling Rate	Recording Rate
DR Voltage (3 ϕ)	Volts	0-600	± 1 V	600 Hz	600 Hz
DR Current (3 ϕ)	Amps	0-100	± 1 A	600 Hz	600 Hz
Utility Voltage (3 ϕ)	Volts	0-15 kV	$\pm .1$ kV	600 Hz	600 Hz
Sectionalizer status	Seconds	0-5	$\pm .01$ s	.001 s	.001 s
Recloser status	Seconds	0-5	$\pm .01$ s	.001 s	.001 s
Sectionalizer current	Amps	0-100	± 1 A	600 Hz	600 Hz
Recloser current	Amps	0-100	± 1 A	600 Hz	600 Hz
Sectionalizer voltage	Volts	0-15 kV	$\pm .1$ kV	600 Hz	600 Hz
Recloser voltage	Volts	0-15 kV	$\pm .1$ kV	600 Hz	600 Hz

Other Requirements

- ∞ **DRs (individual and in combinations)**
 - Inverter-based, any prime mover
 - Synchronous generator
 - Induction generator
- ∞ **Load banks**
- ∞ **Feeder system or feeder simulator**
- ∞ **Fault switch**
- ∞ **Fault impedance (load bank)**