

## Cofiring Biomass with Lignite Coal

Darren D. Schmidt, Project Manager Sean I. Plasynski, DOE NETL Project Officer

# Cofiring Biomass with Lignite Coal

Goal: Demonstrate the feasibility of cofiring biomass with a lignite coal in a grate-fired system.



## Project Objectives

- Perform a technical and economic feasibility study on cofiring wood waste with lignite at the North Dakota State Penitentiary.
- Obtain the first research data on the impact of cofiring biomass fuels with lignite coal
- Provide a demonstration to other state institutions and small stoker-fired systems.
- Provide research data for lignite utilities.



## Basic Project Phase Budgets

- Phase 1 Feasibility Study, \$200,000 total (\$160,000 DOE, \$40,000 North Dakota State Penitentiary)
- Phase 2 Demonstration, \$1.5 million



## Project Members

- EERC
- DOE
- North Dakota State Penitentiary (North Dakota Department of Corrections and Rehabilitations)
- North Dakota Department of Community Services
- King Coal Furnace Corporation
- K.J. Schwartz Engineering



#### NDSP Steam Plant

- Fires 2600–2800 tons/yr lignite coal, 72% efficiency.
- Saturated steam at 100 psig is provided seven months of the year (shutdown May-October).
- Capacity of 200 psig, 28,000 lb/hr.
- Backed with two gas boilers and fitted with an electrostatic precipitator.
- Coal is 1½ stoker coal @ 34% moisture, 6% ash, 43% carbon, 3% hydrogen, 0.3% sulfur, 0.7% nitrogen, 13% oxygen, 7240 Btu/lb.
- Annual cost of operation: \$48,000 (with 2600 tons/yr @ \$18.50/ton).



### Available Local Biomass

- 500 tons/yr of municipal solid waste from the City of Bismarck's landfill.
- Residuals from a local pallet manufacturer.
- Waste paper from state facilities.



# Project Task Structure Phase 1 – Feasibility

- Task 1 Local Biomass Resource Assessment
- Task 2 Fuel-Handling Issues
- Task 3 Fireside Issues
- Task 4 Environmental Issues
- Task 5 Energy Production Assessment
- Task 6 Engineering Economic Analysis




# Project Task Structure Phase 2 – Demonstration

- Task 7 Project Planning and Site Preparation
- Task 8 Engineering Design and Preliminary Fuel-Handling Equipment Testing
- Task 9 Procurement and Construction Activity
- Task 10 Start-Up Equipment Testing
- Task 11 Demonstration Testing, Data Collection, and Analysis




# Project Timeline






# Conceptual Cogeneration Plant






# King Coal Biomass-Handling System





### King Coal Chain Grate Stoker Modification





## Project Members

- EERC
- DOE
- University of North Dakota Facilities
- University of North Dakota Chemical Engineering Department
- North Dakota Department of Community Services



### **UND Steam Plant**

- Fires 45,000 tons/yr (subbituminous) for over 200 buildings.
- Saturated steam at 130 psig is provided year-round.
- Three water tube spreader stoker boilers (13,000 lb/hr coal, 65,000–75,000 lb/hr steam).
- Four gas-/oil-fired boilers (three at 60,000 lb/hr steam, one at 30,000 lb/hr).
- Separate multicyclone units with a common sidestream baghouse for emissions control.
- Coal is subbituminous, 2 x ¼ stoker coal @ 8500
   Btu/lb, 0.6% sulfur, 8.3% ash, 25% moisture.




#### Available Local Biomass

- 13,000 tons/yr of yard waste and brush, diverted from the Grand Forks City Landfill.
- University of North Dakota generates 300 tons/yr waste paper, as well as wood and municipal solid waste.
- Potential cost savings of \$337,000/yr, paying off a \$1.7 million investment in 5 years.




# Current Fuel Consumption for Electric Power in the U.S.






# Potential Use of Biomass for Electrical Generation



## Results of Quantification



20% MSW

26% Ag residue

18% Manure

2% Sludge



