

# Commissioning Building Systems



U.S. DEPARTMENT OF ENERGY  
OFFICE OF ENERGY EFFICIENCY AND RENEWABLE ENERGY

THE FEDERAL ENERGY MANAGEMENT PROGRAM'S

DESIGN STRATEGIES FOR LOW-ENERGY, SUSTAINABLE, SECURE BUILDINGS

A DOE/FEMP Workshop, San Diego, CA. • March 26-27, 2003

Dr. Malcolm Lewis, PE  
President  
CTG Energetics, Inc.  
Irvine, CA  
[www.CTGEnergetics.com](http://www.CTGEnergetics.com)



# Commissioning Building Systems

Dr. Malcolm Lewis, PE  
President  
CTG Energetics, Inc.  
Irvine, CA  
[www.CTGEnergetics.com](http://www.CTGEnergetics.com)




# Commissioning Outline

- What is Commissioning (“Cx”)?
- Why is it Necessary & Critical?
- What are the Elements of Cx Process?
- What are the Key Challenges?

# Context for Commissioning Process

- Fractured design and construction process creates confusing and conflicting relationships between project players



# Definitions of Commissioning

- Commissioning is:
- “...a systematic, documented, and collaborative process including inspection, testing, and training.”
- “...conducted to confirm that a building and its component system meet the requirements of the occupants and conform to the design intent.”
- “...a quality assurance procedure applied to building construction throughout the entire project...”



# LEED and Commissioning

- LEED's Perspective:
  - ◆ Commissioning is so critical that it is required.
- Basic Commissioning – Pre-Requisite
- Additional Commissioning – 1 Credit

# Characteristics of a Commissioned Building

A Commissioned Building:


- ◆ Achieves performance goals
- ◆ Minimizes Energy Consumption
- ◆ Minimizes Environmental Impacts
- ◆ Maximizes Occupant Health & Comfort
- ◆ Optimizes Life-Cycle Costs

# Why is Cx so Critical?

- Buildings are very complex systems
  - ◆ Especially “high performance” buildings
  - ◆ Innovative systems need more support to reduce technical risks
- Without Cx:
  - ◆ Building systems not working properly
  - ◆ Projected savings not achieved
  - ◆ Indoor Environment not adequate
  - ◆ “High Performance” not really “High”



# Bateson Building, Sacramento CA



26-27 March 2003

Sustainable Buildings Industry Council

Malcolm Lewis, PE






Hewlett-Packard Foundation Headquarters, Menlo Park CA  
Architect

# Benefits of Commissioning

- Construction Efficiency
- Energy Efficiency
- Overcoming Technical Risks of Innovation
- Improved Indoor Environmental Quality (IEQ)
- Occupant Productivity
- Reduced Liability Claims
  - ◆ Design
  - ◆ IAQ

# Value of Commissioning HVAC Systems

*Even short-term commissioning can substantially improve energy efficiency.*





# Problems that Commissioning Solves

- Design Goals/Criteria Forgotten or Distorted
- Designs Aren't shown Completely as Intended
- Construction Deviates from Design
- Systems Not Fine-Tuned at Start-Up
- Operators Not Properly Trained
- Systems Not Maintained

# Commissioned Systems in a Green Building


- Lighting Controls
- Sun Controls / Shading
- Demand Controlled HVAC / Ventilation
- Ventilation Systems and Control
- Gray Water
- Storm Water Control
- Photovoltaics / Cogeneration / Fuel Cells
- Direct Digital Controls (DDC)
- Central Plants
- etc.

# What are the Elements of Cx Process?

- Decision to do Commissioning
- Designation of Commissioning Provider
- Integrating Commissioning into the Project
  - ◆ Design
  - ◆ Construction
  - ◆ Post-Construction

# Role of Commissioning Provider

- Focused on Commissioning Activities, not Design details
- Separate function from design
- Knowledgeable in functional areas
- Team Player
- Less effective if not involved EARLY






# Commissioning Documentation

- Design Intent Document
- Commissioning Schedule
- Functional Test Plans
- Specifications
- O&M/Training Info
- Commissioning Report
- Monitoring & Verification Reports


# Design Intent Document

- Set Original Goals for Performance:
  - ◆ Energy Performance
  - ◆ Environmental Performance
  - ◆ Comfort
  - ◆ Operating Cost
- Determine how Performance vs. Goals is to be Measured

Projected Site Energy Savings for the Santa Monica Public Safety Facility




Estimated Energy-Related Pollutant Emissions for the Santa Monica Public Safety Facility



# Verify that Design Intent is Met

- in Design
  - ◆ Verification of Goals in Documents
  - ◆ Coordination between Design
  - ◆ Disciplines
- in Construction
  - ◆ Procurement of Equipment and Materials
  - ◆ Installation
- at Start-Up and Testing
- in Operations



# Start-up and Testing

So Energy Resource Center  
Wl tects

## ■ Operational Testing


- ◆ Static Testing to Ensure Proper Installation
- ◆ Functional Testing to Measure Performance
  - System Capacity
  - Control Strategies
  - Energy Efficiency



# Start-up and Testing (cont)


ation of Temperature monitoring equipment

- Validate/calibrate performance measurement
  - ◆ Energy
  - ◆ Environmental
- Train Building Operators
  - ◆ How Systems Work
  - ◆ How to Operate Systems
  - ◆ How to Maintain Systems



# Training Activities

- Coordinated by Commissioning Provider
- Included in Specifications
- Formal Classroom Training of Operators
- Follow-On Training



SMU Office Building, Sacramento  
Will Raddon

# Commissioning Challenges

- Comprehension
- Commitment
- Integration
- Budget
- Schedule
- Procurement
- Technical
- Follow-Through



SMI Headquarters

# Commissioning Challenges: Comprehension

- Of the need
  - ◆ “Isn’t the design good enough?”
  - ◆ “I already pay for QA/QC and Start-Up and TAB”
- Of the process





Pittsburgh Convention Center, Pittsburgh PA  
Rafael Viñoly

# Commissioning Challenges: Commitment


- Include all disciplines & participants
  - ◆ Owner
  - ◆ Design Team
  - ◆ Contractors
  - ◆ Operators
- Include Cx from the beginning
- Stick with it!

# Commissioning Challenges: Budget

- Cx costs 2-4% of Systems Commissioned
  - ◆ 0.5 - 1% of Total Project Construction Cost
  - ◆ Depends on Scope, Project Size
  - ◆ Depends on Level of Cx
- Pay now or Pay More Later!
- How to minimize?
  - ◆ Avoid duplication with tasks already in someone's Scope
  - ◆ Make Cx part of the project expectations from the start.
  - ◆ Involve O&M Staff in Cx




4 Times Square, New York  
Fox & Fowle Architects



# Commissioning Challenges: Schedule

- Schedule Cx Activities throughout
  - ◆ Involve Commissioning Provider early
  - ◆ Begin Commissioning Process in the design phase
  - ◆ Allow for iterative design refinement
  - ◆ Allow time to correct deficiencies found by testing
- Cx *will* be on the Critical Path at the end

# Typical Commissioning Schedule





SCC Resource Center, Downey CA  
WLC Projects

# Commissioning Challenges: Integration

- Throughout design & construction
- Role of Commissioning Provider
  - ◆ CA is part of the Team.
  - ◆ Don't "shoot the messenger!"
  - ◆ Finding problems is a Success in Cx!
    - The problems have to get fixed by the Construction Team.

# Commissioning Challenges: Procurement

- Design-Build puts Cx under Contractor
  - ◆ Potential conflict of interest
- Low Bid procurement
  - ◆ Requires a very tight Cx Spec



Ford Motor Auto Group Headquarters, Irvine CA  
LPA Projects

# Commissioning Challenges: Technical

- What level of Cx is desired or needed?
- Many new technical challenges with innovative new systems.
- How do you commission Shell & Core Systems when T/I's not done?
  - ◆ Shell - HVAC
  - ◆ T/I - Underfloor Air



# Commissioning Challenges: Follow-Through

Getty Center, Los Angeles CA  
Richard Rogers

- Operations Staff:
  - ◆ Understanding Design Intent
  - ◆ Participating in Commissioning Process
  - ◆ Implementing Operating Strategies
  - ◆ Maintaining Trained Operators on Staff
  - ◆ Monitoring Operations against Performance Goals





Gap Inc. Headquarters, San Bruno, CA  
Willoughby (Design) Gensler (Production)

# Summary

- Commissioning “bridges the gap” between Possibility & Reality
  - ◆ Verifies that Design Intent is Met
  - ◆ Monitors Construction Compliance with Intent
  - ◆ Assures Systems Operate as Intended
  - ◆ Validates/Calibrates Performance Measurements
  - ◆ Trains Operators

# Summary

- Key Elements of Successful Commissioning
  - ◆ Committed Owner and Team
  - ◆ Commissioning Provider present Early in project
  - ◆ Team Approach to Design & Construction
  - ◆ Early O&M Personnel Involvement

# Resources

- FEMP Building Commissioning Guide
- NAVFAC Commissioning Web Site



## BUILDING COMMISSIONING GUIDE

VERSION 2.2

*Sponsored by:*



U.S. General Services Administration  
Public Buildings Service  
18th and F Streets, NW  
Washington, DC 20408

and



U.S. Department of Energy  
Federal Energy Management Program  
1000 Independence Ave., S.W.  
Washington, DC 20585

July 30, 1998

<http://www.eere.energy.gov/femp/techassist/bldgcomgd.html>

# Copyright Notice

Images in this Power Point presentation have been included for non-commercial, educational use only. Except for limited non-commercial, educational use by instructors, these images may not be reproduced, stored in a retrieval system or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, scanning, or otherwise, except as permitted under sections 107 or 108 of the 1976 United States Copyright Act, without the prior written permission of the respective publishers. This includes posting of illustrations on web sites.